

FMFOOT/FMLFOOT/FMTWIN - MINI, LARGE AND TWIN FEET

Description:

Feet for mounting support



FMFOOT



FMLFOOT



FMLFOOT

OTHER ADDITIONAL INFORMATION

Summary of TUV Test Report



Incoming Release Note

Date of Receipt

Test Items

Not Formally Released

9 September 2016

Twin Minifoot with 250mm Channel

Minifoot 110mm

Minifoot 160mm with base

3

N/A

N/A

Customer Defined

Customer Defined

None

9 September 2016

Number of Items tested

Model/Part Numbers

Serial Numbers

Test Plan/Issue/Date

Test Specification/Date

Deviations from the Standard

Date of Test

Test Descriptions

Test 1: Twin Minifoot with 250mm Channel: 100kg load applied (2 x SWL) to sample for 30 minutes duration. Upon completion of the aforementioned test a 1,350kg load was applied.

Test 2: Minifoot 110mm: 50kg (2 x SWL) load applied to sample for 30 minutes duration. Upon completion of the aforementioned test a 1,350kg load was applied.

Test 3: Minifoot 160mm with base: 100kg (2 x SWL) load applied to sample for 20 minutes duration. Upon completion of the aforementioned test a 1,350kg load was applied.

Results of Test

Test 1: The Twin Minifoot with 250mm Channel sample showed no signs of damage after the 100kg and 1,350kg load tests.

Test 2: The minifoot 110mm sample showed no signs of damage after the 50kg and 1,350kg load tests.

Test 3: The minifoot 160mm with base sample showed no signs of damage after the 100kg and 1,350kg load tests.

This Certificate relates only to the actual item tested.

The tests above were applied to the test samples as a vertical compressive load using an MTS 842 Compression Machine.100kg